


Before You Construct an On-site Sewage System

Facts a homeowner should know



Before You Construct an On-site Sewage System

Facts a homeowner should know



In cooperation with
Waste Water Nova Scotia Society

Halifax, Nova Scotia
2000

Preface

The cost of on-site services is usually small compared to the cost of a house or cottage, but a home is worth little without properly designed and functioning systems for disposal of wastewater and distribution of water. If you plan to build a new home or cottage, or if you plan to buy a home or cottage with an existing on-site sewage disposal system, this booklet can help you. The more familiar you are with the information in this booklet, the more likely you are to be satisfied with your system and with your home.

Nova Scotia Department of Environment and Labour administers the On-site Sewage Disposal Systems Regulations. Regional offices are listed for your convenience at the end of this booklet. Staff will be happy to provide you with general information or to answer specific questions about system approval, construction, maintenance, and about the regulations.

Table of Contents

An On-site Sewage Disposal System for Your Home

What is an On-site Disposal System?	1
How does a Septic Tank Work?	2
How does a Disposal Field Work?	4
What are Interceptors?	6

Planning an On-site Sewage Disposal System

Where do I Obtain Background Information for my Area?	6
What do I Have to do as a Property Owner?	7
Who are Qualified Persons?	9
What are Qualified Persons' Responsibilities?	9
What are Licensed Sewage Installers' Responsibilities?	9
What are Environment and Labour's Responsibilities?	9

Contracting the Job

How do I Select a Qualified Person?	12
How do I Select An On-site Sewage Installer?	12

Buying an Existing System

How do I Locate the System if No Documents are Available?	13
How do I Recognize Potential Problems?	14

Caring for your On-site Sewage System

Why Should I Look After my On-site System?	14
How Should I Care for my On-site System?	14
Why and How Should I Conserve Water?	15
What Should Not Go Down the Drain?	15
What Should I Do if a Problem Occurs?	17
The House and Sewer Line	17
The Tank	17
The Field	17
How Can I Make My System Work Better?	18
How Long Is My System Under Warranty?	19

Summary	20
----------------	----

References	21
-------------------	----

Appendix 1	
Sample Form: Application for Approval	22
Sample Form: Submission Standards for Application	25
Appendix 2	
Sample Form: Certificate of Installation	28
Appendix 3	
Sample Form: Maintenance Record	29
Notes or Sketches	30
Nova Scotia Environment and Labour Regional Offices	32
List of Figures	
1. Components of a Typical On-site System	1
2. Components of a Typical Septic Tank	3
3. Components of a C2 Disposal Field and Typical Interceptor/Swale	5
4. Approval Procedure Flowchart for an On-site System	8
5. Example of a Septic Tank Effluent Filter System	19
List of Tables	
1. Minimum Horizontal Clearance Distances Required in the On-site Sewage Disposal System Regulations	10
2. Minimum Horizontal Clearance Distances that Should be Maintained Where Possible	11
3. Minimum Clearance Distances for Wells	11
4. Some Do's and Don'ts to Keep in Mind	20

An On-site Sewage Disposal System for your Home

If you live in the country or a small community, or if you have a cottage or recreational property, you probably have an on-site sewage disposal system, sometimes called a septic system, and a water system from a well. These systems serve properties that are not directly connected to municipal sewer or water systems.

Nova Scotia Department of Environment and Labour regulates the disposal of on-site sewage. Its regulations protect the health of the public and of the environment. Department personnel administer the regulations.

Qualified Persons (QPs) in the private sector are involved in the areas of selection, design, installation, and repair of on-site systems. Information on their qualifications and responsibilities, and how to select one, is given in more detail later. Department personnel audit the work of QPs to make sure that it meets the regulations.

If you have an on-site system, this booklet will help you:

- understand how your system works
- learn how to take care of it to save you money and time.

What is an On-site Disposal System?

An on-site system is basically a recycling system that uses natural processes to treat and dispose of the 'sewage' or wastewater from normal activities in your home. A typical on-site system includes a septic tank and a disposal field (sometimes called a soil absorption area or leach field) that work

An on-site disposal system treats and disposes of wastewater from your home.

together to treat the wastewater. Figure 1 shows an example of a modern system.

Other types of systems still exist. For example, some homes or cottages may have holding tanks or privies, which provide no treatment. The sewage must be pumped out frequently and treated somewhere else off-site.

The on-site system is built to handle certain types and certain amounts of wastewater. It treats both 'blackwater' (toilet wastes) and 'greywater' (wastes from the kitchen sink, bath and showers, laundry, etc.). Extra 'clear' water, from sources such as roof drains, footing and foundation drains, basement sumps, and water treatment units should not be discharged to the on-site system as this extra water does not need treatment and may overload your system. Make sure you know what your system is designed to handle. The section titled Caring for an On-site Sewage System talks about this in detail later.




Figure 1 **Components of a Typical On-site System**

On-site disposal systems differ in detail according to local site conditions, but all must meet specifications of Environment and Labour. When properly designed, installed, used, and maintained, your system will be simple, economical, and effective, and will do its work reliably, safely, and efficiently for many years. If it is poorly designed or installed, or if you use it improperly or don't take care of it, your system can fail. If it fails, it could:

- contaminate a water supply or water used for human consumption
- contaminate a watercourse, wetland, or marine waterbody
- harm human health.

Also, if it fails, repairs could cost you a great deal.

How Does a Septic Tank Work?

Wastewater from the house usually flows by gravity through a building sewer pipe into the septic tank as shown in Figure 1. In some types of systems wastewater is pumped from the house to the tank.

The tank must resist corrosion. Acceptable materials include reinforced concrete, fibreglass, or polyethylene. Tanks that are made of steel corrode over time. If you have a steel tank, you should plan to replace it. The tank must conform to Canadian Standards Association CAN/CSA-B66-M90 (or the most recent update).

The tank must be watertight. It must have an access so that it can be maintained, inspected, and pumped out. The access cover must be watertight and secure to keep unauthorized persons and children out, and to minimize health and safety hazards.

The tank is designed to store the wastewater for a day or more before discharging it to the disposal field or to further treatment. During this time, the

The septic tank holds sewage long enough for solids to settle or float, and for bacteria to break down some of the solids naturally.

heavier sewage solids settle to the bottom to form a **sludge** layer. Lighter solids, fats, greases, and oils float to the top to form a **scum** layer on top of the water. This leaves a middle layer of partially clarified liquid wastewater as shown in Figure 2.

The storage time serves two purposes:

- It allows the solids and liquid to separate, which prevents the solids from being carried into the disposal field and clogging the field and surrounding soil.
- It allows time for bacteria naturally found in the wastewater to break down or digest the solids. This process takes place without the presence of oxygen, and produces gases that must be vented from the tank. Since bacteria reduce the amount of sludge and scum by less than half (approximately 40 per cent), the tank must be pumped regularly to remove the rest of the solids.

An outlet baffle in the septic tank allows only the partially clarified liquid in the middle layer to leave the tank. This liquid is called **effluent**. It still contains bacteria, suspended and dissolved organic solids, and other materials that can be dangerous to health and to the environment. The effluent is discharged to the **disposal field**, which distributes it into the soil for further treatment and disposal.




Figure 2 **Components of a Typical Septic Tank**

How Does a Disposal Field Work?

Effluent normally flows from the septic tank to the disposal field by gravity because the water level in the tank is higher than the level in the field. Distribution pipes to the field are watertight. The pipes within the field are made of perforated PVC or ABS plastic pipe. Longer systems or systems that cannot be gravity-fed need siphons or pumps and pressure distribution piping to distribute effluent evenly into all parts of the disposal system.

The disposal field distributes the effluent evenly at a rate at which the soil can accept the liquid.

Disposal fields consist of several components (Figure 3), each with a different job.

- **Sod:** protects against frost and erosion, sheds surface water, and stores surface water that soaks in until it evaporates or is used by plants.
- **Clean local fill or imported sand fill:** supports the sod and helps its work, and allows oxygen and other gases to pass into and out of the disposal field. If imported sand fill is required, it must meet specific permeability and size requirements.
- **Geotextile (synthetic barrier material):** prevents the backfill material from moving down into the crushed rock and clogging the openings between the rock particles.
- **Perforated distribution pipe:** distributes the effluent evenly to all parts of the field through regularly spaced holes.
- **Crushed rock:** surrounds and protects the pipe, and stores and distributes the effluent over the disposal area.
- **Filter sand:** provides a place at the boundary between the sand and crushed rock for a biological clogging mat which will form after a number of months of operation. This sand must meet specific permeability and size requirements.

- **Natural soil:** acts as the final filter to remove harmful organisms before the effluent reaches groundwater, which may supply a well or discharge into a stream or lake.

As the effluent trickles slowly from the pipes into the field, and eventually into the natural soil, the components of the field and the associated soil microorganisms work together to treat the wastewater. Harmful bacteria are physically filtered out and also destroyed by soil microorganisms. Some dissolved components in the effluent are taken up by plants, adsorb (stick) to soil particles, or are broken down by soil bacteria. When the effluent finally leaves the system, it should not harm public health or the environment.

There are various types of disposal field designs, depending on site conditions. A qualified person evaluates the conditions when selecting or designing a system. Most systems now installed are contour (C1, C1 raised, C2, C2 raised, C3, and mound) types. Figure 3 shows an example of a C2 system. Older systems were usually area bed or multiple-trench type.

For all systems, regulations specify that a minimum thickness of unsaturated soil must be maintained between the bottom of the disposal field and water table, impermeable soil, bedrock, or other features that may limit proper movement or filtering of the

The soil and its microorganisms work together to turn effluent into clean water.

effluent (Figure 3). If the natural soil is too coarse to protect the groundwater, a built-up disposal system with an additional layer of imported sand fill is required over the coarse soil. If the natural soil is too fine

to allow vertical movement of effluent, imported sand fill must be brought in to provide an adequate distribution area.




Figure 3 **Components of a C2 Disposal Field and Typical Interceptor/Swale**

Most or all of the effluent will eventually reach the water table. Systems are designed to ensure that effluent is properly treated in the field and natural

The effluent will be properly treated if the system is kept in good working order and is not overloaded.

soil and that harmful bacteria are removed before it reaches the water table beneath the disposal field. In cases where effluent moves laterally, the natural soil or imported fill or both should provide enough treatment. Also, the area immediately

downslope of a system should be covered with grass or natural vegetation to allow the treated effluent to travel in the root zone and not on the ground surface.

What are Interceptors?

Interceptor drains intercept and divert surface water and shallow groundwater upslope of a disposal field. They help to prevent soil erosion and field waterlogging. Interceptors are not required on all lots. An interceptor can be a swale (shallow trench) at the ground surface, or it can be a trench filled with crushed rock and containing a perforated pipe, as shown in Figure 3.

Foundation and roof drainage should be directed away from a disposal field. This drainage should not be connected to the interceptor drain, although the pipe may be laid in the same trench as the interceptor.

Detailed technical information about on-site systems is available. Copies of the Technical Guidelines can be purchased from Environment and Labour and Waste Water Nova Scotia Society.

Planning an On-site Sewage Disposal System

If you are looking for a lot, remember before you buy that steep slopes, bedrock, streams, water bodies,

If you are looking for a lot, check background information for the area.

and marshes may cause construction and drainage problems. On-site systems on such lots are likely to cost more. Before finalizing any purchase, check available information.

Where Do I Obtain Background Information for My Area?

The type of material beneath the ground surface in your area (soil and surficial geology mapping) can provide you with a general idea of soil permeability. Maps are available from various government agencies. The following people can also provide you with helpful information:

- **Local qualified persons and installers.** Drawing on their experience in the area, QPs and contractors can supply information on the procedure for selecting/designing an on-site system.
- **Environment and Labour staff.** Staff can provide information on geology, general information respecting on-site systems in the area, and the procedure and approvals required to construct an on-site system.
- **Nearby homeowners.** Ask them about their on-site systems.

If you already have a lot, plan what the completed lot will look like before you start to build. Each lot

If you have a lot, know the regulatory requirements and plan ahead.

must be assessed individually to determine the soil conditions where the disposal field is to be located. Soil conditions can vary widely, even over the area of one lot. All buildings and

on-site services must meet applicable regulations. For example, horizontal separation distances to wells, streams, property lines, and other features are regulated and are designed to minimize adverse environmental effects. A qualified person (QP) will assess the lot and make sure regulations are followed before seeking an approval.

What Do I Have to Do as a Property Owner?

A general overview of the start-to-finish procedure to obtain an approved system is outlined below and summarized in Figure 4. You do NOT have to carry out all these steps yourself, but as the property owner you ARE responsible to see that they are done:

Assessment

- Get an application for approval form and a list of QPs from your nearest Environment and Labour office (locations are listed in the back of this booklet). Appendix 1 shows an example of the form.
- Hire a QP (see the following section to find out who qualifies) who will assess the property, select or design a system, and complete and sign the application form. You must also sign the form.

Application

- Mail or drop off the completed application form to the local development office or Environment and Labour office yourself, or have your agent do so. In Halifax Regional Municipality (HRM), the form must be returned to the nearest HRM office; other areas may differ, so check on the protocol for your area. The department charges an administration fee for each application.

- Processing will normally take a few days while staff review the application; they may visit the site. If the information on the completed form is satisfactory, approval for installation will be given for the system selected or designed by the QP. If the application is incomplete, it will be returned with a letter outlining what is missing. The process will begin again once the corrected form is submitted.
- When approved, four copies of the approval are issued. Environment and Labour keeps the original and sends a copy to the QP. You as the applicant receive two copies, one of which is for your records, the other for the installer. In HRM, you must make another copy and take it to the municipality to have a building permit issued. Make sure you have your copy of the approval and any other permits.

Installation

- You or your agent then hire a certified installer to install the system according to the terms and conditions specified on the approval.

Inspection

- Your QP must verify that the installation meets the terms and conditions of the approval. The Department of Environment and Labour must be notified three days before the system is covered so that an inspector can check the installation if they wish.
- Spread topsoil and seed or sod over the disposal field immediately to prevent erosion. This will be one of the terms and conditions of the approval. Your QP will do another inspection to ensure that topsoil is placed.
- After the final inspection and covering of the system, the QP must complete a certificate of installation form. Appendix 2 shows the form to be used.

Final details

- The QP distributes copies of the certificate to you as the owner, Environment and Labour, and the installer and keeps one for him/herself. In HRM, a fifth copy must be filed with the municipality in order to obtain an occupancy permit. Make sure you have your copy.

Once the system is installed, you as the homeowner or applicant have the biggest role in keeping it working. Four ways to do this are:

- Make sure that the topsoil and seed or sod cover is in place.
- Make sure that you know where the septic tank, its covers, and the disposal system are located for future maintenance. Make sure that landscapers who work on the property later know where all parts of the on-site system are located so that they don't disturb it or drive over it.
- Make sure that the interceptor drains are maintained and not filled in, redirected, or otherwise destroyed by later landscaping.
- Make sure that the system is properly maintained as outlined later in this booklet.

Finally, make sure your paperwork is in order. Keep certificates, measurements, diagrams or sketches, and other information related to the system with your deed or in a separate, readily accessible on-site services folder. If you sell the property later, make sure that the information is given to the next owner.




Figure 4 **Approval Procedure Flowchart for an On-site System**

Who Are Qualified Persons?

Qualified persons (QPs) can select or design a system for you. System selection involves choosing a system from Environment and Labour's technical guidelines if site conditions, such as soil type, slope, depth to water table, and depth to bedrock, match those in the guidelines. System design involves making changes to the systems in the guidelines if site conditions do not match those exactly, or for larger systems, or for modifications other than emergency repairs to existing systems. There are two types of QPs:

- Qualified Persons Level I (QPIs) can select or design systems. QPIs are professional engineers who are registered to practise in Nova Scotia and who hold valid liability insurance.
- Qualified Persons Level II (QPILs) can select systems, but not design them. QPILs are technical persons other than professional engineers who hold valid liability insurance, and who have been properly trained and certified.

There is a section later on how to select a QP.

What Are Qualified Persons' Responsibilities?

Under the regulations, QPs must provide information to Environment and Labour as part of the application for approval (sample form in Appendix 1). At the appropriate time, the QP performs the final inspection of the system and submits additional information as part of the certificate of installation (sample form in Appendix 2).

Lot layout requires careful planning to ensure that all regulatory and recommended separation distances are maintained. For your information, these distances are summarized in Tables 1 and 2 on pages 10 and 11. The well location must also meet separation distances required by the Well Construction Regulations, summarized in Table 3 on page 11. Your QP is responsible to ensure that your system is properly located and installed according to regulations.

What Are Licensed Sewage Installers' Responsibilities?

Licensed installers have the following responsibilities:

- Make sure that a valid approval (Appendix 1) exists for the on-site sewage disposal system before installation.
- Make sure that the exact contour is followed.
- Make sure that septic tank, fill, pipe, and geotextile meet regulatory specifications.
- Install the system according to the approval obtained.
- Contact Environment and Labour before any variation is made to an approval.
- Contact the QP for an inspection before covering the sewage disposal system.
- Cover septic tank with 15–150 cm (6–60 in.) of soil. Cover disposal system with 30–46 cm (12–18 in.) of approved sand, and cover sand with 10–15 cm (4–6 in.) of a good grade of topsoil.
- Include the price of topsoil in the contractor quote to the homeowner. Topsoil and seed or sod cover must be in place before a final inspection is approved.

What Are Environment and Labour's Responsibilities?

Design, selection, construction, and ownership of an on-site sewage system are governed by the Environment Act and the On-site Sewage Disposal Regulations. Anyone found violating the act and/or regulations is subject to prosecution under the Summary Offence Act. If convicted, they could be fined at least \$675. You can view the regulations at your local Environment and Labour office, or download them from the web: (www.gov.ns.ca/just/regulations/regs/env5197.htm).

The department and its Inspector Specialists have the following responsibilities with respect to on-site systems:

- Provide lot/subdivision information to the public.
- Review the applications submitted by QPs to ensure that all information is included and that selections/designs follow approved standards and guidelines.
- Audit all aspects of the process through to installation, including field inspections if necessary.
- Assist and guide newly certified QPs with the entire process through a mentoring program to make sure that the work is done to standards.
- Enforce the department's regulations respecting on-site sewage disposal systems.

Table 1 **Minimum Horizontal Clearance Distances Required by the On-site Sewage Disposal System Regulations¹**

From	To	Distance (metres)	Distance (feet)
System, including septic tank and disposal field ⁶ , holding tank or privy	Any lot boundary	3	10
	Lot boundary downslope from disposal field	9	30
	Drilled well with at least 6.1 m (20 ft) of casing ²	15.2	50
	Dug well ^{2,3} or any other water supply	30.5	100
	Watercourse ⁴ or wetland ⁵ or marine waterbody	30.5	100
	Downslope ditch or drain that flows intermittently, except drains or ditches that form an integral part of the system	15	50
	Municipal or private water distribution system	6	20
	Artificially created body of water	15	50
Disposal Field ⁶	Minimum vertical separation distance between the bottom of the disposal field and any bedrock, maximum groundwater table, or any other limiting conditions ⁸	1	3.3
Septic tank, vault privy, or holding tank	Foundation drainage system ⁹	1.5	5
Disposal field or pit privy	Foundation drainage system ⁹	6	20

Notes:

- (1) An inspector may require greater distances if adverse effects may be created, and shall provide reasons in writing.
- (2) See also Tables 2 and 3, and note 7 below.
- (3) A dug well includes a drilled well with less than 6.1 m (20 ft) of casing.
- (4) Watercourse means the bed and shore of every river, stream, lake, creek, pond, spring, lagoon or other natural body of water, and the water therein, within the jurisdiction of the Province, whether it contains water at all times or not.
- (5) Wetland means lands commonly referred to as marshes, swamps, fens, bogs, and shallow water areas that are saturated with water long enough to promote wetland or aquatic processes and marine water bodies, which are indicated by poorly drained soil, vegetation, and various kinds of biological activity that are adapted to a wet environment.
- (6) Separation from disposal field should be measured from nearest edge of the trench.
- (7) Whenever possible, disposal systems should not be located immediately upslope of wells. When planning proposed subdivision layouts, it is important to consider relative locations of wells and disposal systems to avoid problems as lots become developed.
- (8) A perched water table is considered a limiting condition.
- (9) Foundation drainage system includes both the system around the home AND the discharge pipe, whether perforated or not.

Table 2 **Minimum Horizontal Clearance Distances that Should be Maintained Where Possible¹**

From	To	Distance (metres)	Distance (feet)
Disposal field ⁴	Downslope boundary		
	• Category 2 lot ²	15	50
	• Category 3 lot	25	82
	• Category 4 lot	30	100
	Downstream sudden increase or break in slope		
	• Category 1 lot	5	16
	• Category 2 lot	10	33
	• Category 3 lot	15	50
	• Category 4 lot	20	66
	Manmade pond	15	50
Wells immediately downslope ^{3,5}	100	330	
Downslope foundation	20	66	

Notes:

- (1) An inspector may require greater distances if adverse effects may be created, and shall provide reasons in writing.
- (2) The lot category determines its area and minimum width. Category is NOT related to the type of system (C1, C2, etc.). Category is determined by soil type, permeability and depth, whether any part of the system will be within 60 m (200 ft) of water (lake, stream, river, ocean), and the maximum daily flow. Lot area and width may be increased when flows exceed 1500 litres per day (330 gallons per day).
- (3) A dug well includes a drilled well with less than 6.1 m (20 ft) of casing.
- (4) Separation from disposal field should be measured from nearest edge of the trench.
- (5) Whenever possible, disposal systems should not be located immediately upslope of wells. When planning proposed subdivision layouts, it is important to consider relative locations of wells and disposal systems to avoid problems as more lots become developed.

Table 3 **Minimum Clearance Distances for Wells^{1,2}**

From	To	Distance (metres)	Distance (feet)
Cesspool (receiving raw sewage)	Drilled or dug well	61	200
Seepage (leaching pit), filter bed, soil absorption field, earth pit, privy or similar disposal unit	Drilled well	15.2	50
	Dug well	30.5	100
Septic tank, concrete vault privy, sewer of tightly joined tile or equivalent material or sewer-connected foundation drain	Drilled well	15.2	50
	Dug well	30.5	100
Sewer of cast iron with leaded or approved mechanical joints, independent clear water drain, or cistern	Drilled or dug well	3	10
Pumphouse floor drain, cast iron with leaded joints, draining to ground surface	Drilled or dug well	610 mm	2
Vertical extension of the centre line of the well from any projection of a building	Drilled or dug well	1.6	5.2
Property boundary	Drilled or dug well	1.5	5
Outer boundary of any road or public highway as defined in the Public Highways Act	Drilled or dug well	6.1	20
Landfill, garbage dump or other source of contamination (if written approval is granted for well construction)	Drilled or dug well	61	200

Notes:

- (1) See also note (5) in Table 2.
- (2) A dug well includes a drilled well with less than 6.1 m (20 ft) of casing.

Contracting the Job

How do I Select a Qualified Person?

To find out whether you are most likely to need a QPI or a QPII, contact the nearest Environment and Labour office for advice. Once you know that, check for the following:

- ✓ Does the QPI have a valid licence from Association of Professional Engineers of Nova Scotia?
- ✓ Does the QPII have a valid certificate of qualification from Environment and Labour?
- ✓ Does the QP (I or II) have appropriate liability insurance?

A list of QPs can be obtained from your local Environment and Labour office or web page (www.gov.ns.ca/envi/DEPT/qpersons.htm).

How Do I Select An On-site Sewage Installer?

Under the On-site Sewage Regulations, any person constructing or repairing on-site systems must have an up-to-date certificate of qualification from Environment and Labour. The certificate is renewed every year.

Nova Scotia has approximately 700 certified installers. Most operate within a one- to three-county radius. Experienced contractors who have worked in the area will be most familiar with local conditions.

Prior to selecting a contractor for the job, it is a good idea to obtain information from and about several contractors. Check for the following:

- ✓ Does the contractor have a valid certificate of qualification from Environment and Labour?
- ✓ Does the contractor have adequate equipment in good condition to do the job?
- ✓ Does the contractor have adequate liability and worker's compensation insurance to protect you?
- ✓ Is the contractor familiar with applicable health and safety codes?
- ✓ What is the contractor's reputation with previous customers?

Once the contractor is selected, keep in mind that:

- If terms and conditions of the approval must be changed due to unforeseen problems or conditions encountered during construction, discuss the options with your QP and the contractor. Approval for any changes must be obtained from Environment and Labour.
- Changes may mean additional costs.

Any person constructing or installing or repairing on-site systems must have a valid certificate of qualification from Environment and Labour. Every septic tank cleaner must also be registered with the department.

Buying an Existing System

For a house purchase, banks and mortgage companies now usually request a certificate from a QP that the on-site system was installed according to Environment and Labour standards, or a copy of the certificate of installation showing details of the on-site system (Appendix 2). Houses built before 1985 may not have certificates, and records prior to 1995 are poor. In short, the responsibility is YOURS.

Before buying an existing home, you should check the following:

- Find out where the existing wastewater system and water supply are located and get complete information about them before completing the purchase. Inspection by a trained person is strongly recommended, especially if little or no information or documentation is available.
- Find out exactly where property boundaries are and be sure there is enough room to replace or modify wastewater systems if necessary.

Ask for answers to a few important questions such as:

- How old is the system?
- When was the septic tank last pumped?
- How frequently has it been pumped?
- Have there been signs of possible failure?

How do I Locate the System if No Documents are Available?

Contact your local Environment and Labour or municipal office and ask if there is a copy of the approval for your property on file. Before calling, know the previous owner's name, approximate date the current system was installed, and civic address. If there is no information on file:

- Look in the crawl space or basement area to see the direction in which the building sewer pipe enters the soil. Measure the distance from the sewer pipe to the corner of the outside wall from inside the house, then the same distance along the same wall on the outside of the house.
- Locate the septic tank by pushing a thin (1.0 to 1.3 cm (3/8 to 1/2 in.) diameter) steel rod into the soil to feel for the tank, which is usually about 3 m (10 ft) from the house and 0.6–0.9 m (2–3 ft) below ground surface. Before digging or probing, call Nova Scotia Power Inc. at 1-800-428-6230 to make sure that there are no underground utilities such as buried electrical cables in the area. Be careful of overhead utility lines as well.
- To locate an older area bed disposal field, start searching downslope from the septic tank. If the system has a pump, the field can be upgradient of the tank, but this situation is not common. Probe the ground every couple of feet with an insulated probe until you hear the metal rod contact gravel or the probe is wet (when testing is not during a rainy period), and flag that point. Repeat to locate additional drainfield lines (usually 0.9–1.5 m or 3–5 ft apart and 15–30 m or 50–100 ft in length). Take careful measurements and sketch locations on a grid or graph paper for future reference. Pages 29 and 30 are included for this purpose.

Some manufacturers and consultants offer electronic transmitters to assist with locating the septic tank. Metal detectors are another possibility with old systems or metal tanks.

How Do I Recognize Potential Problems?

Although not foolproof, some possible warning signs of a system that is not working properly include:

- plumbing backups or sewage backups in the house (toilets, drains, etc.)
- toilets that take longer to flush, showers and sinks that take longer to drain. Flush each toilet to observe whether it drains quickly or not. Run water in every sink and observe whether it drains freely or sluggishly. If only one fixture is slow, the problem is likely related to that individual fixture.
- gurgling in the plumbing
- breakouts or discharge of raw sewage to the ground surface, especially after a heavy rainfall. Breakouts are often indicated by wet spots or ponding or grey or black liquids or black soil areas in the area of the disposal field or nearby ditches.
- noticeable unpleasant or sewage odours around the yard, or in the vicinity of the disposal field, especially after a rainfall
- lush green growth over the disposal field. Grass over the system becomes unusually green or spongy to walk on, even during dry weather.
- buildup of aquatic weeds or algae in lakes or ponds or ditches adjacent to your home
- the presence of nitrates or bacteria in the well water. It is wise to have the well water tested for bacterial and chemical quality, as recommended in the companion booklet *Before You Construct a Water Well*.

If you notice any of the signs above, get professional advice before finalizing the purchase. Repairs or replacement, if necessary, can be costly.

Caring for Your On-site Sewage System

Why Should I Look After My On-site System?

On-site systems are generally cheaper to install and maintain than central services, but they do require more care and attention by the owner. When properly installed and looked after, on-site systems

A well-maintained septic system can run for decades.

An abused or neglected one can fail tomorrow.

can reliably dispose of household sewage in a way that will protect your water supply, public health, and the environment.

Improperly designed, selected, installed or maintained systems can fail.

Repair or replacement of a failed on-site system is expensive. Cutting costs in the care or maintenance of your system, or careless use of a system, will usually cost you more in the long run. A poorly maintained or malfunctioning system can reduce the resale value of your property.

How Should I Care for My On-site System?

Solids accumulate in a septic tank over time. When a tank is allowed to fill near or past its capacity, sludge or excess solids can migrate into the disposal field and block

the pipes. The tank inlet may also get blocked, and cause sewage back up into the home. Repairs can range from clearing a few lines to replacing entire disposal fields and landfilling contaminated soil.

Costs can vary from a few hundred to a few thousand dollars.

Inspect the tank every year or two and have it pumped regularly, at least every 3 years. Have the tank pumped by a registered septic tank cleaner.

The average septic tank should be inspected every 1–2 years to determine depth of sludge and scum. If the cover is removed and the tank is full, this does not mean there is a malfunction. The tank is designed to have the outflow level approximately 75 mm (3 in.) below the inflow level.

- If the distance between the bottom of the pipe coming from the house and the liquid level (NOT the scum level) is less than this, then either drainage is restricted somewhere in the system, the field is unable to handle the volume of effluent, or groundwater is leaking into the tank.
- If the distance between the bottom of the pipe coming from the house and the liquid level is greater than this, then the liquid in the tank is leaving the tank somewhere other than the pipe leading to the disposal field.

The tank should be pumped out to remove solids every 3 years, or when required, depending on the amount of use and the type of materials that enter the system. Regular inspection may indicate that an individual tank can be pumped less frequently, while tanks that are heavily used or abused may need to be pumped more often. Grease traps should be inspected regularly. If the grease chamber is half-full, the tank should be pumped by a registered septic tank cleaner. After you uncover the tank, the tank cleaner will pump the contents into a truck and dispose of it in an approved manner. The tank should not be washed or disinfected. Operation of pumps and siphons should be routinely checked by a certified person.

Summer and early fall are the best times to pump out a regularly used septic tank. This will leave time before winter for the tank to refill and for bacterial action to re-establish. Also, in the fall the ground will not be frozen, and high water table, which can create buoyancy problems for septic tanks, is usually not a factor. Tanks in seasonal systems should not be emptied before winter because they may be damaged by frost.

Septic tanks are often not maintained either because the location of the tank is unknown or it is so deeply buried that access is difficult. If no records are available, measure and record the location of the tank covers with reference to the corners of the house next time the tank is serviced. If access is deep, a riser with watertight joint can be installed over the manhole of the tank to bring the access to,

or near, the surface. This makes regular inspections, monitoring and maintenance easier.

NEVER enter an empty septic tank yourself. The gases in the tank could be fatal!

Never enter the tank yourself. The gases in the tank, such as methane and

hydrogen sulphide, can be explosive or toxic to workers. An open flame or flashlight with more than two cells should not be used in or near a septic tank because of the danger from the explosive gases. People have died of asphyxiation in septic tanks and sewers. The liquid in the tank should also be treated with respect. Sewage may contain bacteria, viruses, or parasites that can make people sick.

The disposal field must also be properly cared for. The sod cover should be maintained to prevent erosion and to reduce the amount of rainfall that enters the field. Large trees should be removed from the immediate area of the field to prevent roots from clogging the pipes, short-circuiting effluent to the surface or damaging the system (if the tree is uprooted).

It is important not to cover the field with a hard surface, such as concrete or asphalt or heavy clay material. Vehicles (cars, machinery, ATVs, snowmobiles) must NOT be allowed to run over any part of a disposal field since soil compaction, crushed distribution pipes, and damage to the field can result. Don't stack wood or build a shed or raised garden over your disposal system. The soil needs to breathe.

For trouble-free operation, you should also control how much water you use and what goes down the drain.

Why and How Should I Conserve Water?

Water conservation shows good management. The minimum design capacity of a residential on-site system, which could

include seasonal and rental units, is 1000 L/day (220 gpd). If you have a larger home, or if your home has fixtures that use additional water (such as hot tubs), or if you have a commercial establishment, you will need a system designed for higher flows. If the system receives more wastewater than it is designed for, problems can result. For example:

- The excess flow can wash out solids from the septic tank before they are treated or removed, damaging or clogging the disposal field.
- If excess flow is more than the field can disperse, the ground surface or your plumbing system may flood.

Conserving water will extend the life of your system.

What Should Not Go Down the Drain?

An on-site system can handle all normal household wastes, including body wastes, wash water, and laundry wastewater (including some bleach). However, some materials should not go down the drain because:

- an on-site system cannot treat them and they may contaminate water supplies or the environment
- they will affect or slow down the performance of the system, and result in extra maintenance or repair, or require system replacement. Some materials that should not go down the drain are listed in Table 4 on page 20.

Use commercial household and bathroom cleaners in moderation. They can damage your system. Many people clean their toilets, sinks, showers, and tubs with a mild detergent or baking soda. Do not use caustic drain openers for a clogged drain. Instead, use boiling water or a drain snake to open clogs. Consider using an environmentally friendly alternative product (Environment and Labour has a pamphlet available).

Septic tank additives are not needed for proper operation of the tank. They may damage the system and contaminate groundwater. Some additives cause solids to wash from the septic tank into the disposal field. This is not recommended because the solids could clog the field.

Garbage grinders should not be used unless the size of the septic tank is increased by 20 per cent to handle the extra solids.

Backwash water from water treatment devices is a controversial subject. Some research suggests that this water may cause problems in on-site systems, other research suggests that it may be beneficial. Until more information is available, Environment and Labour does not recommend that you discharge backwash water to the on-site system. If an existing treatment unit is hooked into the on-site disposal system, have a certified plumber check the system for correct and safe installation. A proper air gap is required to prevent wastewater from backing up into the water supply system.

What Should I do if a Problem Occurs

Keep a file folder readily available with a diagram of the system location, approval, and certificate of installation. If you cannot find your records, Environment and Labour may have a copy of the approvals. If no records are available, start your own file.

Keep system information handy! If a problem occurs, your file is invaluable.

A problem or malfunction usually shows up in one of two ways:

- sewage backs up into the household plumbing
- sewage or wet spots appear on top of the ground.

Troubleshooting usually begins in the house and proceeds towards the disposal field.

The House and Sewer Line

Sewage backup into the house, or even fixtures that drain slowly, may mean a physical blockage in the household fixtures themselves. If you have a toilet that won't flush properly or a drain that refuses to empty, start there. A plunger may free the toilet, or cleaning a drain trap may free the sink. These are simple checks you can do yourself.

If these simple measures do not work, hire a certified plumber to check for a physical blockage in the house. Common culprits include rags, diapers, children's toys, plastic bottles, and a combination of congealed grease and lint from the washing machine.

If there is no blockage in the house, the next step is to check the building sewer line between the house and the tank. Common problems in the line include the culprits listed above, frost heave and settling, and broken pipe. Frost heave and settling may have altered the original slope on the sewer line, creating low spots where liquid can puddle and freeze during the winter months. This results in partial restriction or blockage. Alternatively, the pipe may have broken off completely due to settling after installation.

The Tank

If fixtures and sewer line are clear, the next step is usually to have a certified installer or registered septic tank cleaner inspect and pump your septic tank. Key trouble spots for blockage in the septic tank are the inlet and outlet baffles or tees (Figure 2 on page 3). It is important to check that the tank still has baffles. If these have broken down or broken off, scum and solids may have moved into the field and clogged it. If the problem is a blocked or crushed line leading to the tank, or a blocked tank inlet or outlet, it will usually show up when the tank is inspected or pumped.

If pumping the tank does not solve the problem for more than a few days, or if raw sewage is discharging, the problem is likely in the disposal field. If pools of water are noticed in the field area, use water sparingly for a few days and check for improved performance.

The Field

Some common problems related to the field include overloading with water, clogging of some part of the system, or physical damage to the system. Check if any of these apply to your situation.

Increase in water load can result from:

- using fixtures such as hot tubs, jacuzzis, and spas
- concentrating water use, such as multiple washes in one day
- increasing family numbers or entertaining groups or visitors
- leaking plumbing fixtures
- running faucets to prevent freezing of pipes
- piping sink and laundry wastes directly to the field and bypassing the tank
- directing water from roofs, driveways, and foundation drains into the system
- flooding by high groundwater table seasonally
- overloading of part of the field with water, due to too much or too little slope within the field, or ponding and infiltration of surface water over part of the field
- poor design (too small for the flow).

Problems related to the pipes, rock, or soil can result from:

- poor design (system inadequately sized for the soil conditions)
- poor location with respect to the surrounding land or groundwater table such that the effluent cannot escape readily
- too much or too little slope on distribution pipe within the field
- use of improper or inferior materials, such as imported sand fill or filter sand that does not meet specifications (usually permeability too slow)
- installation where the natural permeability of the soil is too low
- construction during wet conditions, leading to smearing and reduction of natural soil permeability on the infiltrative surfaces.

Problems related to physical damage can result from:

- compaction from vehicle traffic or landscaping activities
- paving, building, or storage of objects on top of the field
- tree roots
- carryover of scum and solids from the tank.

If you have an emergency, such as sewage backing up into the house, and you cannot fix it yourself, call a certified installer. Depending on the specific cause(s) of your problem, you may need a QP involved to make further repairs or changes to the existing system, or to select or design a new system. You can also contact the nearest Environment and Labour office (list at the back of this booklet) for advice on how to solve the problem.

How Can I Make My System Work Better?

Some ways to avoid failures and minimize malfunctions, in new and existing systems, include:

- Check and fix or replace leaking or slow-draining plumbing fixtures regularly. Call a plumber if you cannot find the problem yourself.
- Spread out water use: do laundry (full loads) once a day or over the week rather than partial loads or several loads a day. Do dishwashing as the machine is full and spread out the loads. Use water-saving machines.
- When guests or parties will produce an extra load on the system, pump tank before guests arrive. Use off-site facilities for excess laundry. Consider a timed-dose system. If the extra load is regular, you may need to expand the system.
- Reduce normal water use in showers and sinks: take short showers and turn off the water while brushing teeth.
- Use heat tape to prevent freezing of pipes rather than running water continuously.
- Install water conserving fixtures, such as low-flow showerheads and ultra-low flush toilets.
- Make sure that the septic tank is watertight so groundwater does not leak into it.
- Make sure that the system is located and protected to avoid unnecessary extra water from groundwater, surface water, roof and foundation drains, interceptor drains, sumps, treatment unit backwash, and other sources.

Prospective and existing owners should consider two extra components that can improve system performance, make inspection of on-site systems easier, and help diagnose problems. These components are not required now, but they are inexpensive compared with the cost of the system, or with the cost of repairing or replacing it.

- Septic tank effluent filters shown in Figure 5 are designed to intercept solids that might otherwise escape from the tank and clog the field. Filters need regular cleaning, usually when the septic tank is inspected or pumped. If they require more frequent cleaning, it is probable that the materials that blocked the filters would have reached the disposal field, causing potentially serious and expensive damage.
- A water meter will record your water use. You can compare use with the design flow of the system and detect leaking fixtures. The record will help you to make decisions about water conservation. Remember that if use is greater than the design flow rate, untreated effluent may surface downgradient of the field.

How Long is My System Under Warranty?

The warranty period is 18 months. During this time, if there are problems with the on-site system, the original installer will meet with the QP, Environment and Labour representative, and the homeowner to identify the problem and then determine what repairs are required. Whoever is found to be responsible for the problem will pay for the repairs.




Figure 5 **Example of a Septic Tank Effluent Filter System**

Summary

Design, selection, construction, and ownership of an on-site sewage disposal system are governed by the Environment Act and the On-site Sewage Disposal Regulations. Once the system is completed, the homeowner is responsible for care and maintenance. Proper use and regular maintenance are the keys to long-term satisfactory performance of an on-site system. Most failures are due to poor maintenance, or to improper use of the system by the owner – what goes in it, and what goes over it!

Some do's and don'ts are shown in Table 4. If you keep these in mind, your on-site system should provide good service for a long time.

Make sure that you record any repairs and maintenance work carried out on your system. A sample record form is shown in Appendix 3. This information is invaluable for future dealings with a contractor, a government agency, or a future purchaser of your home.

Table 4 **Some Do's and Don'ts to Keep in Mind**

Do's

- Do spread automatic washer use over the week rather than many loads on one day.
- Do make a permanent record of where the key parts of your system are located for future maintenance, such as tank pump outs or field repairs.
- Do have your septic tank pumped out regularly.
- Do keep records of pump outs and maintenance.
- Do use water conserving devices where possible. Low flush toilets and shower heads are commonly available.
- Do have manually cleaned lint traps on your automatic washer.
- Do check any pumps, siphons, or other moving parts of your system regularly.
- Do remove or prevent trees with large root systems growing near the disposal field.
- Do maintain a healthy grass cover over the disposal field to use some of the water and to prevent erosion.
- Do keep surface water from upslope or from roof drains away from the disposal field.
- Do check your interceptor drain regularly to ensure that it is free-flowing.
- Do compost your kitchen waste or include it in your garbage. A garbage grinder should be installed only when the septic tank is oversized, and the tank will need to be pumped more often.

Don'ts

- Don't overload the system with high volumes of water.
- Don't connect basement sump pumps to the on-site system.
- Don't connect backwash from water treatment devices directly to the on-site system without professional advice.
- Don't allow large amounts of fats, chemicals, or solvents to enter the system; don't allow any plastics to enter.
- Don't use septic tank additives. They are not beneficial, and may damage your disposal system. Active bacteria are naturally present in sewage. Even with additives, regular pumping of solids is still required.
- Don't enter a septic tank without proper ventilation, a second person (adult) above ground, and other requirements of the Department of Labour for confined spaces. Sewer gases can be fatal.
- Don't allow vehicles or heavy equipment to drive over or park on the disposal field. This may compact the soil and crush the piping.
- Don't plant anything over the disposal field except grass; especially, don't cover the tank or field with asphalt or concrete or other impermeable material.
- Don't put in a separate pipe to carry wash waters to a side ditch or woods. These 'greywaters' also contain disease-carrying organisms
- Don't wait for signs of failure. Check the system regularly.
- Don't flush:

- coffee grounds	- dental floss	- paints
- disposable diapers	- kitty litter	- varnishes
- sanitary napkins	- tampons	- waste oils
- cigarette butts	- condoms	- poisons
- fats, grease and oils	- paper towels	- thinners
- disinfectants	- pesticides	
- photographic chemicals	- other chemical wastes	

References

Nova Scotia Department of the Environment. 1997.
Before You Construct a Water Well. Report 68-3
(Fifth Revision 1997).

Nova Scotia Department of the Environment. 1998.
Regulations Respecting On-site Sewage Disposal
Systems. Made by the Governor in Council pursuant
to Sections 66 and other regulation making Sections
of Chapter 1 of the Revised Statutes of Nova Scotia,
1994-1995, the *Environment Act*. (revisions
expected in 2000)

Nova Scotia Department of the Environment. 2000.
On-site Sewage Disposal Systems Technical
Guidelines. Interim.

Appendix 1

Sample Form: **Application for Approval**



Department of the Environment

APPLICATION FOR APPROVAL

OFFICE USE ONLY		APPLICATION #	
DATE REC'D (YYYY/MM/DD)	EXT. REF. #		NSDOE FILE
TOTAL FEES DUE	FEES PAID	PAID IN	YES NO
RECEIPT #	WATER AUTH. # (DIV 1 ONLY)		

PLEASE PRINT OR TYPE. Complete Sections 1, 2, 3, 4 and 7 for ALL Applications. Complete areas of Sections 5 and 6 that are applicable to the specific activities of this application only.

TYPE OF APPLICATION:			
NEW APPLICATION	<input checked="" type="checkbox"/>	RENEWAL	<input type="checkbox"/>
AMENDMENT	<input type="checkbox"/>	TRANSFER	<input type="checkbox"/>
IF APPLICABLE, PROVIDE THE PREVIOUS APPROVAL # _____			

SECTION 1 - OWNER

If there is more than one owner, please indicate who will be the primary applicant for this project and attach a complete list of owners.

Company/Organization/Municipality							
Business Number (BN), if applicable							
Mr.	<input checked="" type="checkbox"/>	Ms.	<input type="checkbox"/>	Mrs.	<input type="checkbox"/>	Other	<input type="checkbox"/>
Professional Designation							
First Name	John			Middle Initial	Family Name		
Smith							
Phone	Home	(902) 999-9999	Business	()	Ext.	Other	()
Fax		()	E-mail				
Civic/Street Address							
100 Smith's Lane							
Mailing Address (if different than Civic)							
County				City/Town			
Halifax				Smithtown			
Province			Postal Code		Country		
Nova Scotia			BOB 0B0		Canada		

SECTION 2 - APPLICATION CONTACT

Is the Application Contact the same as Section 1 - Owner? Yes No If yes, please skip to Section 3

Company/Organization/Municipality							
Professional Consultants Inc.							
Business Number (BN), if applicable							
Mr.	<input checked="" type="checkbox"/>	Ms.	<input type="checkbox"/>	Mrs.	<input type="checkbox"/>	Other	<input type="checkbox"/>
Professional Designation				QP II			
First Name	Joe			Middle Initial	Family Name		
Jones							
Phone	Home	()	Business	(902) 000-0000	Ext.	Other	()
Fax		(902) 000-0000	E-mail				
Civic/Street Address							
100 Professional Drive							
Mailing Address (if different than Civic)							
County				City/Town			
Halifax				Smithtown			
Province			Postal Code		Country		
Nova Scotia			BOB 0B0		Canada		

SECTION 3 - SITE/LOCATION OF PROPOSED ACTIVITIES

Property Identification Numbers (PID) are available at the Nova Scotia Department of Housing & Municipal Affairs.
1:50,000 Topo Maps (Identifying Easting and Northing) are available at Nova Scotia Department of the Environment Regional Offices.

Subdivision Name <u>Deer Park</u>	
Lot # <u>10</u>	
Site name <u>8 Deer Drive</u>	
Civic/Street Address	
County <u>Halifax</u>	Community <u>Smithtown</u>
Property Identification # (PID) <u>999 99 999</u>	1:50,000 Topo Map # <u>11012</u>
Grid reference	Easting (6) Northing (7)

SECTION 4 - ACTIVITY

Proposed Activity - Please check (✓) all that apply.		
<u>Activity</u>		<u>Complete Sections</u>
On-site Sewage Disposal System	<input checked="" type="checkbox"/>	4, 5A, 6, 7
Subdivision Proposal Report	<input type="checkbox"/>	4, 5B, 6, 7
Lot Assessment report	<input type="checkbox"/>	4, 5B, 6, 7
Will this Activity employ new technology?	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
If yes, please specify.		
Proposed Project Dates, if applicable (yyyy/mm/dd)		
Start Construction Date	Start Operations	End/Closure Date

SECTION 5 - ACTIVITY DETAILS

Complete Section 5 to the best of your knowledge. Please provide measurements in metric units where indicated.

5A - Complete for all <i>Individual Lot</i> On-site sewage only.								
Sewage Disposal System	New	<input checked="" type="checkbox"/>	OR	Replacement	<input type="checkbox"/>			
Size of Lot	Length (meters)	<u>120+/-</u>	Width (meters)	<u>60+/-</u>	Area (meters ²)	<u>7500+/-</u>		
Water Supply	Existing	<input type="checkbox"/>	OR	Proposed	<input checked="" type="checkbox"/>			
Type	Dug Well	<input type="checkbox"/>	Drilled Well	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>		
If other, please specify:								
Type of building	New	<input checked="" type="checkbox"/>	Existing	<input type="checkbox"/>				
Dwelling type	Single Detached	<input checked="" type="checkbox"/>	OR	Other	<input type="checkbox"/>	If other, please specify		
Number of Bedrooms	<u>3</u>	Design Capacity (litres/day)	<u>1000</u>	Whirlpool Baths/Hot tubs	Yes	<input type="checkbox"/>	No <input checked="" type="checkbox"/>	
Name of Qualified Person (if applicable)					Certificate/APENS #			
Category of Lot	1	<input type="checkbox"/>	2	<input checked="" type="checkbox"/>	3	<input type="checkbox"/>	4	<input type="checkbox"/>
Municipal Planning Approval	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	Date of Approval (yyyy/mm/dd)	<u>2000/08/31</u>		
Assessment Report completed by:	QP 1	<input type="checkbox"/>	QP 2	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>		
If other, please specify								

5B - Request for Written Report for a Subdivision Proposal or Lot Assessment (Report only - no Approval issued)	
Is this a Development Officer request for a written report?	Yes <input type="checkbox"/> No <input type="checkbox"/>
Proposed Number of	Proposed Lot Numbers (attach list if

SECTION 6 - SUPPORTING DOCUMENTATION TO ATTACH

All supporting documentation is to be submitted in accordance with the "Approvals Procedures Regulations". If applicable, the following documents must be submitted with this Application; however, additional information may be requested.

Note: A legend must be supplied for all mapping describing symbols used, scale and north orientation.

Attach for All applications	
	Copy of the property deed, lease or letter providing the applicant's legal right to conduct the activity on the site
✓	Sketch of lot(s), including (but not limited to): - Location of proposed buildings, wells, septic systems, roads and driveways - Distances (meters) to wells and septic systems, watercourses, wetlands, etc within 60 meters of property lines.
	Copy of subdivision, surveyor's or plot plan
	If applicable, Qualified Person's Assessment Reports and Qualified Person's Selection (system type, size, location, etc)

If information submitted is incomplete, or if supporting documentation is of poor quality (plans, maps, etc), the application may be delayed, returned or rejected.

SECTION 7 - DECLARATION

Correspondence is to be returned to:	Owner <input checked="" type="checkbox"/>	OR	Application Contact <input checked="" type="checkbox"/>
Information in this application package which the applicant considers to be confidential business information should be clearly identified. Are you making this request?			
Yes <input type="checkbox"/>		No <input checked="" type="checkbox"/>	
If yes, please indicate which information in the Supporting Documentation is considered confidential.			

Owner's signature	<u>John Smith</u>	Date (yyyy/mm/dd)	<u>2000/09/30</u>
Name (Please print or type)	<u>John Smith</u>		
OR Owner's Authorization (Letter of Authorization attached)			
If you are acting on behalf of the owner, you must:			
1. Attach a letter of authorization from the Owner identified on Page 1, Section 1, of this application.			
2. Identify yourself as the Application Contact on Page 1, Section 2, of this application.			
3. Sign the declaration below			
I certify that I am acting with the owner's full consent.			
Signature	<u>Joe Jones</u>	Date (yyyy/mm/dd)	<u>2000/09/30</u>
Name (Please print or type)	<u>Joe Jones</u>		

Sample Form: **Submission Standards for Applications Form**

February 10, 2000


SUBMISSION STANDARDS FOR APPLICATIONS FORM

All applications must comply with the Act, Regulations, Guidelines and any policies within the Department. A completed copy of this form should accompany each application.

APPLICANTS NAME: John Smith APPLICATION #: _____
 SUBDIVISION NAME: Deer Park LOT NUMBER: 10

SITE EVALUATION OF LOT

*Sketch of lot, location of soil evaluation tests, direction of slope, watercourse and other features that may influence the selection or design of the system.



SOIL EVALUATION TESTS

TEST PIT PROFILE (M)

TOTAL DEPTH:	1.5 M
BEDROCK AT:	unknown M
WATER TABLE:	unknown M
SLOPE:	10 %
ROOTS TO:	0.500 M
MOTTLING AT:	none M


SOIL STRATUM	SOIL TYPE	DEPTH OF SOIL (mm)	DENSITY	MOISTURE
ORGANIC	organic mat	150	loose	damp
1 ST layer	Sandy silt	375	loose	damp
2 ND layer	Clayey silt	975	medium to tight	water seepage at top of layer
3 RD layer				

Permeability of soil in-situ:	n/a
Flow rate:	n/a
Test method:	n/a

APPLICANTS NAME: John Smith APPLICATION #: _____

SYSTEM SELECTION CRITERIA			
Daily flow <u>3 bedroom house</u>	Soil Type	Soil permeability	Depth of permeable soil
Litres/day: <u>1000</u>	<u>Sandy silt</u>	m/s: <u>3×10^{-6}</u>	mm: <u>375</u>

SYSTEM SELECTION FROM TECHNICAL GUIDELINES			
Type of Disposal Field:	<u>C2 raised</u>	Imported sand fill required	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
Dimensions: metres	<u>43 L x 0.9 W</u>	Permeability Rate	<u>5×10^{-5} to 8×10^{-4}</u> m/sec
Cut at Toe of Trench:	<u>100 mm</u>	Width of Buffer -downslope -upslope	<u>5 M</u> <u>3 M</u>
Interceptor Trench	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO depth: <u>600mm</u>	Depth of Buffer	<u>at 5m, 300 mm</u>
Pump or Siphon Capacity	<u>no</u> Litres	Septic Tank Capacity	<u>4750</u> Litres




* Cross sectional diagrams of proposal to be attached to this form for submission.

DATE: 2000/09/30 QUALIFIED PERSON: Joe Jones

CERTIFICATE OF QUALIFICATION #: 9999 (SIGNATURE)
Joe Jones
(PRINT NAME)

SCHEDULE C C2 RAISED



Total length = 43m
Trench width = 0.9m
Total width of field = 9.8m

Refer to site plan and guidelines for exact location and separation distances.

End of the interceptor must extend to the point where water can freely drain to the surface



DISPOSAL FIELD SPECIFICATIONS	
as above	N/A
as above	Top soil seed or sod
as above	Clean local backfill
as above	Barrier material
75	Crushed rock above pipe
100	Perforated pipe diameter
33	Perforated pipe length
125	Crushed rock below pipe
75	Filter sand
$\frac{1 \times 10^{-4}}{8 \times 10^{-4}}$	Filter sand permeability
minutes at 20°C	minutes at 20°C
0.600	Interceptor swale depth

General Conditions
Contractor shall verify location of all wells, watercourses, lot boundaries and all elevations prior to construction (within 30.5 m from the location of disposal system)

Backwash water from water treatment must not be discharged to the on-site sewage disposal system.

Disposal system must be installed by a contractor licensed to install on-site sewage disposal systems in Nova Scotia.

All work must be completed in accordance with a Nova Scotia On-Site Sewage Disposal Systems Regulations, On-Site Sewage Systems Technical Guidelines, and conditions of this approval.

Roof, foundation and lot drainage must be directed away from the disposal field, septic tank and pump (siphon) chamber.

Steps must be taken to ensure that the proposed disposal field areas are not subject to vehicular traffic or any other disturbance such as excavation or stockpiling of excavated material etc. Installation of physical barrier is recommended.

It is applicants responsibility to assure that construction of foundations, driveway, well or any other development on the lot will not impact on feasibility of on site sewage disposal field installation.

Contractor is responsible for pump selection and installation (if pump is required by approval.)

NOT TO SCALE

REFER TO GUIDELINES FOR CONSTRUCTION DETAILS

Applicant	John Smith
Approval No:	
Location	Lot 10, Deer Park

Appendix 2

Sample Form: **Certificate of Installation Form**

CERTIFICATE OF INSTALLATION FORM		N.S.D.O.E. Application #
APPROVAL HOLDER		SYSTEM INSTALLER
Name: <u>John Smith</u>		Qualification #: <u>C9900</u>
Address: <u>100 Smith's Lane</u>		Name: <u>Dave Backhoe</u>
<u>Smithtown</u>		Address: <u>200 Professional Drive</u>
<u>NS</u>		<u>Smithtown, NS</u>
Postal Code: <u>BOB0B0</u>		<u>BOB0B0</u>
Phone No.: <u>999-9999</u>		Phone No.: <u>111-1111</u>
Lot: <u>10</u>		Location: <u>8 Deer Drive</u>
C-COMPLIANT	N - NON COMPLIANT	NA - NOT APPLICABLE
TYPE OF <input type="checkbox"/> C1 <input type="checkbox"/> Standard C2 <input checked="" type="checkbox"/> Raised C2 <input type="checkbox"/> C3 <input type="checkbox"/> Mound		
<input type="checkbox"/> Area bed <input type="checkbox"/> Multiple Trench <input type="checkbox"/> Holding Tank <input type="checkbox"/> Other		
not to scale	SKETCH OF DISPOSAL SYSTEM	SYSTEM SPECIFICATIONS
	<p style="text-align: center;">N ↑</p>	System length <u>43</u> Metres System width <u>0.9</u> Metres Pipe quality <input checked="" type="checkbox"/> C <input type="checkbox"/> N Pipe slope <input checked="" type="checkbox"/> C <input type="checkbox"/> N Crushed rock <input checked="" type="checkbox"/> C <input type="checkbox"/> N Excavation <input checked="" type="checkbox"/> C <input type="checkbox"/> N Interceptor ditch <input checked="" type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> NA Barrier material <input checked="" type="checkbox"/> C <input type="checkbox"/> N Imported fill <input checked="" type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> NA Septic Tank <input checked="" type="checkbox"/> C <input type="checkbox"/> N <input type="checkbox"/> NA Watertight <input type="checkbox"/> Yes <input type="checkbox"/> No Pump chamber <input type="checkbox"/> C <input checked="" type="checkbox"/> N <input type="checkbox"/> NA Watertight <input type="checkbox"/> Yes <input type="checkbox"/> No Siphon <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Tested <input type="checkbox"/> Yes <input type="checkbox"/> No Pump Installed <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Tested <input type="checkbox"/> Yes <input type="checkbox"/> No Alarm Present <input type="checkbox"/> Yes <input type="checkbox"/> No
SYSTEM CLEARANCE DISTANCES (M = METRES)		
Distance to Nearest Dug Well _____ M <input checked="" type="checkbox"/> NA	Distance to Nearest Lot Boundary <u>9.1</u>	
Distance to Nearest Drilled Well <u>>15.2</u> M <input type="checkbox"/> NA	Distance to Nearest Downslope Boundary <u>>30</u>	
Distance to Nearest Watercourse _____ M <input checked="" type="checkbox"/> NA	Distance between Foundation Drainage	
Distance to Nearest Wetland _____ M <input checked="" type="checkbox"/> NA	System → Septic Tank <u>2</u>	
Distance to Nearest Ditch or Drain <u>>15</u> M <input type="checkbox"/> NA	→ Distribution trench <u>7.6</u>	
Approval Holders Water Supply <input checked="" type="checkbox"/> Drilled Well <input type="checkbox"/> Dug Well <input type="checkbox"/> Municipal <input type="checkbox"/> Not in Place	Distance from System to Approval Holders Well <u>>15.2</u> M	
Distance from Septic Tank to Approval Holders Well <u>>15.2</u> M		
Comments/ Concerns/ Problems:		
<u>4" of topsoil and seed or sod to be applied over the disposal system</u>		
I Certify that the On-site Sewage Disposal System herein described was inspected on _____ and was installed in accordance with the On-site Sewage Disposal System Regulations and complies with the approval issued.		
Qualification Number: <u>9999</u>		
Signature of Qualified Person: <u>Joe Jones</u> Date: <u>Oct. 28, 2000</u>		

Appendix 3

Sample Form: **Maintenance Record**

My Maintenance Record


Date:	Work performed:	Work performed by:	Cost:

Septic System Installer
Name _____
Address _____
Phone _____
Date System Installed _____
Certificate of Qualification # _____


Septic System Pumper
Name _____
Address _____

Phone _____

Notes or Sketches



Notes or Sketches



Nova Scotia Environment and Labour Regional Offices

REGION	STREET AND MAILING ADDRESS	TELEPHONE NO.	FAX NO.
Central Region Bedford	1595 Bedford Highway Suite 224, Sunnyside Mall Bedford, NS B4A 3Y4	(902) 424-7773	(902) 424-0597
Sheet Harbour	Fire Hall, 22835 Highway #7 PO Box 58 Sheet Harbour, NS B0J 3B0	(902) 885-2462	(902) 885-2743
Windsor	55 Wentworth Road PO Box 567 Windsor, NS B0N 2T0	(902) 798-2096	(902) 798-5096
Shubenacadie	5 Mill Village Road, Suite 208 PO Box 350 Shubenacadie, NS B0N 2H0	(902) 758-2097	(902) 758-7001
Northern Region Truro	44 Inglis Street, 2nd Floor, IGA Building PO Box 824 Truro, NS B2N 5G6	(902) 893-5880	(902) 893-0282
Pictou	Middle River Pumping Station, Granton Road PO Box 675 New Glasgow, NS B2H 5E7	(902) 396-4194	(902) 396-4765
Amherst	32 Church Street, 2nd Floor Amherst, NS B4H 3A8	(902) 667-6205	(902) 667-6214
Western Region Kentville	136 Exhibition Street Kentville NS B4N 4E5	(902) 679-6088	(902) 679-6186
Middleton	32 Commercial Street PO Box 1240 Middleton, NS B0S 1P0	(902) 825-2123	(902) 825-4471
Bridgewater	60 Logan Road Bridgewater NS B4V 3J8	(902) 543-4685	(902) 527-5480
Yarmouth	13 First Street Yarmouth NS B5A 2S9	(902) 742-8985	(902) 742-7796
Lockeport	Hayden Lake Water Treatment Plant PO Box 158 Lockeport, NS B0T 1L0	(902) 875-8630	(902) 875-1221
Eastern Region Sydney	295 Charlotte Street PO Box 714 Sydney, NS B1P 6H7	(902) 563-2100	(902) 563-2387
Port Hawkesbury	Old Pulp Mill Road PO Box 603 Port Hawkesbury, NS B0E 2V0	(902) 625-0791	(902) 625-3722
Baddeck	Provincial Building, Chebucto Street PO Box 6 Baddeck, NS B0E 1B0	(902) 295-2159	(902) 295-2675
Antigonish	Kirk Place, 219 Main Street, Suite 205 Antigonish NS B2G 2C1	(902) 863-7389	(902) 863-7411